

U2 - Infill and Prefab

Objectives:

Trainees ...

- understand and are able to explain the three general different construction-options of a) direct-plastering (loadbearing and hybrid, NSS), b) planking on one side (hybrid, NSS), and c) planking on both sides (infill, SSS)
- understand the needs for weather-protection, airtight and windproof construction and moisture prevention
- know the general low-energy and passive house principles
- know and are able to explain the dis-/advantages of the different techniques according to the needs, budget, safety and the building law

Methods:

- presentation, lecture
- practical training,
- supervising training work

Trainer:

Place:

Workshop

Duration:

2 days

Equipment

wood screws straw bales tools

Н

Е

0

R

T

 Different structural options of infill and prefabrication and their characteristics and bale requirements.

- Fixing bales in different techniques
- Compressing bales in different systems
- Advantages and disadvantages of infill and prefabrication techniques
- Details of connections: foundation, corners, windows and doors, roof, etc.
- Preparing different surfaces for plastering

Documents:

Trainer sheet

T1

Info sheet

I1 How to choose the constructionsystem, different techniques

2 Construction Samples

Text sheet

X1

Slide show

Evaluation

Multiple choice

P

Task

R

C

T


- Working groups with 3-4 TN
- Preparing the wood frame
- Infill straw bales in standing position ("on edge")
- Compress the bales with different techniques
- Fixing the bales in the construction
- Airtight/windproof installation of a window
- Shaving the bales, if necessary
- Preparing bales/boards for plastering

C

Organisation

20 straw bales for each group

Wood parts, boards and joints (screws, nails, brackets, staples) see material list Tools see material list



U2 - Infill and Prefab